

Subdivisions, T.2 N., R. 32 E.

Chains	
79.60	Intersect East boundary 70 links North of corner to secs. 1 and 12, from which I run N. 89° 30' W. on a true line between Secs. 1 & 12.
36.00	Umatilla River, 100 links wide, runs N.W.
39.80	Set stone 16 x 12 x 4 for $\frac{1}{4}$ Sec. corner, from which a Balm 15 in. diam. bears S. 10° E., 290 links dist.
44.00	Umatilla River, 50 links wide, runs S.W.
54.00	Leave timber, bears N.W. & S.E. Umatilla River, 125 links wide, runs N.W.
79.60	The corner to Secs. 1, 2, 11 & 12. Land, level. Soil, 1st rate river bottom. Timber, Cottonwood.
<hr/> North on a random line between Secs. 1 & 2. <div style="text-align: right;">Variation 20$\frac{1}{2}$° East</div>	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.50	Intersect North boundary at corner to Secs. 1 & 2, from which corner I run South on a true line between Secs. 1 & 2. Descend hill.
39.50	Set stone 12 x 8 x 8 for $\frac{1}{4}$ Sec. corner
52.50	Foot of hill, enter timber, bears E & W.
67.00	Umatilla River, 100 links wide, runs West.
79.60	The corner to Secs. 1, 2, 11 & 12 at edge of timber, which bears E & W. Land on South $\frac{1}{2}$ mile, gently rolling; soil, 1st rate; on North $\frac{1}{2}$ half mile, steep and stony; soil 3rd rate. Timber, Cottonwood.
October 31st, 1864.	
<hr/> North between Secs. 34 & 35.	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth, with charred stake, pits &c., as per instructions.