

Subdivisions, T. 2 N., R. 32 E.

Chains		
	Descend hill.	
40.80	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.	
80.80	The corner to Secs. 4, 5, 8 & 9.	300
	Land, hilly.	
	Soil, 2nd rate.	
<hr/>		
	North between Secs. 31 & 32.	
40.00	Set stone 18 x 10 x 6 for qr. sec. corner.	
80.00	Set stone 15 x 10 x 6 for corner to secs. 29, 30, 31 & 32.	
	Land, rolling.	
	Soil, 2nd rate.	
<hr/>		
	East on a random line between Secs. 29 & 32.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.	
79.50	Intersect N & S line 13 links South of corner to Secs. 28, 29, 32 & 33, from which corner I run	
	S. 89° 54' W. on a true line between Secs. 29 & 32.	
13.50	Birch Creek(Dry bed)course N.W.	
39.75	Set stone 12 x 10 x 8 for $\frac{1}{4}$ Sec. corner.	
79.50	The corner to Secs. 29, 30, 31 & 32.	
	Land, rolling.	
	Soil, 2nd rate.	
<hr/>		
	West on a random line between Secs. 30 & 31.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.	
88.30	Intersect West boundary at corner to sections 30 & 31, from which corner I run	
	East on a true line between Secs. 30 & 31.	
	Descend hill.	
48.30	Set stone 20 x 12 x 5 for $\frac{1}{4}$ Sec. corner.	
53.00	Foot of hill.	
88.30	The corner to Secs. 29, 30, 31 & 32.	250
	Land, hilly.	
	Soil, 2nd rate.	