

20
Subdivisions T. 2 N., R. 32 E.

Chains	<p>6 & 7, from which I run</p> <p>S. 89° 30' East on a true line between Secs. 6 & 7.</p> <p>Descend hill.</p>	
47.32	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charr- ed stake, pits &c., as per instructions.	
87.32	The corner to Secs. 5, 6, 7 & 8.	-400
	Land, rolling.	
	Soil, 2nd rate.	
<p>North on a random line between Secs. 5 & 6.</p> <p style="text-align: right;">Variation 20° East.</p>		
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.	
80.80	Intersect North boundary 53 links East of corner to Secs. 5 & 6, from which corner I run	
	S. 0° 23' E. on a true line between Secs. 5 & 6.	
	Descend hill.	
40.80	Set stone 24 x 12 x 10 for $\frac{1}{4}$ Sec. corner.	
80.80	The corner to Secs. 5, 6, 7 & 8.	- 400
	Land, rolling.	
	Soil, 2nd rate.	
	November 4th, 1864.	
<p style="text-align: center;">General Description</p> <p>The land in this Township is generally rolling, grass covered hills. The soil is 1st and good 2nd rate with much good farming land on Birch Creek and Umatilla River bottoms.</p> <p>There is a large amount of timber on the Umatilla River and on the two dry creeks that are in the township.</p> <p>This Township is well watered with streams flowing through it and by numerous springs.</p> <p>There are a large number of settlers. The County Seat of Umatilla County, Oregon is in the N.W. part of Sec. 9</p> <p>The town site embraces about 20 acres and is called Middleton. There are, however, but three houses in the place.</p>		