

Subdivisions, T. 2-N.R., 32 E.

Chains	
39.60	To corner. Land, rolling. Soil, 2nd rate.
<hr/>	
	North between Secs. 13 & 14.
40.00	Set post and made earth mound for $\frac{1}{4}$ Sec. corner.
41.40	Dry bed of creek, N.W.
80.00	Set post and made earth mound for cor. to Secs. 13, 14, 11 and 12. Land, rolling. Soil, 2nd rate.
<hr/>	
	East on random between Secs. 12 & 13. Var. 21° East
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
79.80	Intersected N & S line at corner. West on true line.
39.90	Set post and made earth mound for $\frac{1}{4}$ S. cor.
79.80	To cor. Land, rolling. Soil, 1st rate.
<hr/>	
	North bet. Secs. 11 & 12.
28.00	Wagon Road, E & W.
40.00	Set post and made earth mound for $\frac{1}{4}$ S. cor.
80.00	Set stone 18 x 17 x 6 for corner to Secs. 11, 12, 1 & 2. Land, rolling. Soil, 2nd rate.
<hr/>	
	East on random bet. Secs. 1 & 12. Var. 21° East.
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
80.00	Intersected N & S line 52 links N. of corner. N.89° 40' W. on true line.
35.50	Umatilla River; 100 links N.W.