

Field Notes of the Subdivisions  
of Tp. 2 N.R.32 E. Surveyed by  
Jas. P. Currin and Jas. E. Noland,  
Under their Contract,  
Dated May 4th, 1887.

Chains

Survey commenced July 27th, 1887 with a Burts Improved  
Solar Compass.

I commenced at the corner to Secs. 1, 2, 35 & 36 on S.  
boundary of Township, I run

North on random between Secs. 35 & 36.

Var. 21° East.

40.00 Set temp.  $\frac{1}{4}$  Sec. corner.

79.70 Intersect line 30 links East of old Cor. to Secs. 25,  
26, 35 & 36, which I re-established by setting stone  
20 x 12 x 8 ins., 14 inches in the ground marked with  
1 notch on E. and S. edges; re-dug pits 18 x 18 x 12  
ins., in each section  $5\frac{1}{2}$  ft. distant from stone and  
raised a mound of earth 2 ft. high,  $4\frac{1}{2}$  ft. base over  
it.

Thence S. 13' East on true line.

Var. 21° East.

1.70 Summit of hill.

+90

11.70 Gulch.

-30

14.70 Summit of point.

+40

22.20 Spring Branch, 2 lks. wide. Course W; line passes  
about 2.50 chs. W. of Spring.

39.35 Set stone 16 x 10 x 6 ins., 10 inches in the ground for  
 $\frac{1}{4}$  Sec. corner. Marked  $\frac{1}{4}$  on W. face. Dug pits 18x18x12  
ins. N. and S. from stone  $5\frac{1}{2}$  ft. distant and raised a  
mound of earth  $1\frac{1}{2}$  ft. high,  $3\frac{1}{2}$  ft. base over it.

79.70 To corner to Secs. 1-2-35 & 36.

Land, first  $\frac{1}{2}$  rolling; 2nd  $\frac{1}{2}$ , level.

Soil, 1st rate.

Poor grass.

No timber.

East on random between Secs. 25 & 36.

Var. 21° East

40.00 Set temp.  $\frac{1}{4}$  Sec. corner.

80.00 Intersect Township line 49 links N. of Corner to Secs.