

Subdivisions, T. 2 N. R. 32 E.

Chains		
	dug pits 18 x 18 x 12 ins. N. and S. from stone $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
68.00	Intersect U. R. bdy., and set post 4 ft. long, 4 ins. square 24 ins. in the ground for U. R. Closing Corner, marked T. 2 N.R.32 E. U.R. C.C. on N. face, S.34 on E. and S.33 on W. faces. Dug pits N.E. and W. 18 x 18 x 12 ins. $5\frac{1}{2}$ ft. dist. from post and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base alongside.	
80.00	To cor. to Secs. 3, 4, 33 & 34. Land, rolling. Some grass. Soil, poor. Scattering Cottonwood along creek.	
<hr/>		
	East on random bet. Secs. 27 & 34. Var. 20° East.	
40.00	Set temp. $\frac{1}{4}$ Sec. cor.	
80.00	Intersect East bdy. 25 links N. of Corner to Secs. 26, 27, 34 & 35. Thence N. 89° 49' W. on true line. Va. 21° 30' East.	
17.50	Summit of hill.	+20
38.50	County Road Pendleton and Pilot Rock.	
40.00	Set stone 10 x 8 x 7 ins., 7 ins. in the ground for $\frac{1}{4}$ Sec. corner, marked $\frac{1}{4}$ on N. face, dug pits 18 x 18 x 12 ins. E & W from stone $5\frac{1}{2}$ ft. dist. over which I raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base.	
80.00	To Cor. to Secs. 27, 28, 33 & 34. Land, rolling. Soil, 1st rate. No timber or grass.	
<hr/>		
	West on random bet. Secs. 28 & 33. Var. 20° East.	