

Subdivisions, T. 2 N. R. 32 E.

Chains	
40.00	<p>alongside.</p> <p>Set stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{2}$ on W. face; dug pits 18 x 18 x 12 ins. N & S. from stone $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p>
80.00	<p>To cor. to Secs. 28, 29, 32 & 33.</p> <p>Land, rolling.</p> <p>Soil, good.</p> <p>No timber; poor grass.</p>
<p>East on random bet. secs. 21 & 28</p> <p style="text-align: right;">Var. 20° 30' East.</p>	
40.00	<p>Set temp. $\frac{1}{4}$ Sec. cor.</p>
80.00	<p>Intersect E. bdy. at Cor. to Secs. 21, 22, 27 & 28. Thence W. on true line.</p> <p style="text-align: right;">Var. 20° East.</p>
25.50	<p>Enter field.</p>
31.75	<p>McKay Creek, 5 lks. wide. N.W.</p>
40.00	<p>Set stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ Sec. Corner, marked $\frac{1}{2}$ on N. face; dug pits 18 x 18 x 12 ins. E. & W. from stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p>
44.15	<p>Leave Creek bottom and ascend.</p>
79.50	<p>Wagon Road, Course N.E.</p>
80.00	<p>To Cor. to Secs. 20, 21, 28 & 29.</p> <p>Land, rolling.</p> <p>Soil, 1st rate.</p> <p>Cottonwood and thorn along creek. Poor grass.</p>
<p>West on random bet. Secs. 20 & 29.</p> <p style="text-align: right;">Va. 20° 30' East.</p>	
80.00	<p>Set temp. $\frac{1}{4}$ Sec. corner.</p> <p>Intersect at cor. to secs. 19, 20, 29 & 30. Thence East on true line.</p> <p style="text-align: right;">Var. 21° East.</p>