

Subdivisions, T. 2 N.R. 32 E.

Chains	
40.00	Set a post 4 ft. long and 4 ins. square, 24 ins. in the ground for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ S. on N. face and raised a mound of stone over it. Pits impracticable.
42.50	Gulch.
69.00	Intersect U.R.bdy. Set stone 10 x 10 x 12 ins., 8 ins. in the ground for U.R. Closing Corner, marked S. 20 on N. and S. 29 on S. face, U.R.C.C. on E. face. Dug pits 18 x 18 x 12 ins. E.N. & S. from stone $5\frac{1}{2}$ ft. dist. and raised mound of earth alongside 2 ft. high, $4\frac{1}{2}$ ft. base.
72.50	Wagon Road, fence and field. Course N & S.
78.50	Wagon Road.
80.00	To Cor. to Secs. 20, 21, 28 & 29.
	Land, rolling.
	Soil, 1st rate.
	No timber; poor grass.
North on random bet. Secs. 20 & 21.	
	Var. 20° 30' East.
40.00	Set temp. $\frac{1}{4}$ Sec. cor.
80.00	Intersect N. bdy. at old Cor. to Secs. 16, 17, 20 & 21. Repaired old corner. Set a post 4 ft. long, 4 ins. square 24 ins. in the ground, marked T.2 N. S. 16 on N.E., R.32 E. S.21 on S.E., S.20 on S.W., and S.17 on N.W. faces with 5 notches on E. and 3 on S. edges. Dug pits 18 x 18 x 12 ins. in each Sec. $5\frac{1}{2}$ ft. dist. and raised a mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base alongside.
	South on true line bet. Secs. 20 & 21.
	Var. 20° 15' East.
10.00	Dry ditch or gulch.