

Field Notes of the Survey of Donation Land  
 Claim No. 38, of Wm. C. McKay, T.2, N.R.32 E.,  
 Made by Daniel Chaplin, under Special Instructions  
 Dated Oct. 6, 1864.

Chains	I begin at a post set for SW corner in mound of earth with charred stake, pits &c., as per instructions, and run North on West boundary.
65.50	Set post for corner, from which a Balm 18 in. bears S.30° W. 22 links dist. " " 12 " " S.43° E. 29 " " Thence East;
5.00	Set post for corner from which A Balm 12 ins. diam. bears S.30° E. 26 links dist. " " 20 " " " N.73° W.83 " " Thence North;
7.00	Umatilla River.
13.50	Intersect line between secs. 5 & 8, 20.00 chains West of corner to Secs. 4, 5, 8 & 9.
14.50	Set post for N.W. corner in mound of earth with charred stake, pits &c., as per instructions. Thence East on North boundary.
20.00	Line between Secs. 4 & 5, 100 links North of corner to Secs. 4, 5, 8 & 9.
40.00	Set post for N.E. corner in mound of earth with charred stake, pits &c., as per instructions. South on East boundary.
1.00	Line between Secs. 4 & 9, 20.00 chains East of corner to Secs. 4, 5, 8 & 9.
14.50	Set post for corner in mound of stone; Thence West;
5.00	Set post for corner from which A balm 18 ins. diam. bears N.45° W. 5 links dist. " " 20 " " " N.30° E. 8 " " Thence South on East boundary.
17.50	Umatilla River runs N.W.
65.50	Set post for S.E. corner in mound of earth with charred stake, pits &c., as per instructions. Thence West on South boundary.