

S. bdry. T. 1 S.R. 33 E.

Chains		
80.00	<p>Set post for corner to secs. 2, 3, 34 & 35 in mound of earth with charred stake, pits, trench &c., as per instructions.</p> <p>Land, level creek bottom.</p> <p>Soil, 1st rate.</p> <p style="text-align: right;">September 16th ?</p>	
<p>East on North boundary of Sec. 2.</p> <p style="text-align: right;">Variation 20° East.</p>		
40.00	<p>Set $\frac{1}{4}$ Sec. post in mound of earth with charred stake, pits, trench &c., as per instructions.</p>	
55.00	<p>Ascend East slope of Blue Mountains.</p>	
80.00	<p>Set stone 18 x 12 x 5 in. for corner to secs. 1, 2, 35 & 36.</p> <p>Land on West, 55.00 chains level; soil 1st rate. On East, 25.00 chains steep and stony; soil 3rd rate.</p>	<p>+500</p>
<p>East on North boundary of Sec. 1.</p> <p style="text-align: right;">Variation 20° East.</p>		
<p>Ascend hill.</p>		
40.00	<p>Set stone 36 x 12 x 5 for $\frac{1}{4}$ Sec. corner.</p>	
80.00	<p>Set post for corner to Townships 1 & 2 North Ranges 33 & 34 East in mound of earth with charred stake, pits, trench &c., as per instructions.</p> <p>Land, steep and stony.</p> <p>Soil, 3rd rate.</p> <p style="text-align: right;">September 17th, 1864.</p>	<p>+1000</p>
<p style="text-align: center;">E. Boundary, T. 2 N.R. 33 E.</p>		
<p>North on East boundary of Sec. 36.</p> <p style="text-align: right;">Var. 20° 30' East.</p>		
<p>Descend along East slope.</p>		
40.00	<p>Set stone 15 x 10 x 8 in. for $\frac{1}{4}$ Sec. corner.</p>	
55.00	<p>Deep canon bears East & West.</p>	