

## N. Bdy. T. 2, N., R. 33 E.

Chains

Reservation but the lines of the Reservation have never been surveyed and the exact boundary is not known.

---

Field Notes of the Exterior  
Boundaries of T. 1 N. R. 33 E.  
By Z. F. Moody, Under Contract  
Dated April 23, 1871.  
North Boundary.  
(S. Bdry. T. 2. N.R. 33 E)

---

West on a random line on North boundaries of Sections  
1, 2, 3, 4, 5 & 6.

Var. 21° East.

I set temporary half mile and mile posts at every 40 and 80 chains, and at 5 miles, 70 chains to a point 1 chain and 50 links North of the corner to Townships 1 and 2 North Ranges 32 & 33 East.

Found the post and set it in old mound.

N. 89° 50' East on true line on North boundary of Sec. 6.

Var. 19° 30' East.

39.00 Set post and raised mound of earth for  $\frac{1}{4}$  Sec. corner.

79.00 Set post and raised earth mound for cor. to Secs. 5, 6,  
31 & 32.

Land, level.

Soil, 1st rate. Good grass.

---

North 89° 50' East on true line on North boundary of  
Section 5.

Var. 19° East.

40.00 Set post and raised mound of earth for  $\frac{1}{4}$  Sec. corner.

80.00 Set charred stake and made mound of earth for corner to  
Secs. 4, 5, 32 & 33.

Land, level.

Soil, 1st rate. Good grass.

---

North 89° 50' East on true line on North boundary of  
Section 4.

Var. 18° 30' East