

N. Boundary T. 2 N. R. 33 E.

Chains	
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
80.00	To corner.
	Land, rolling.
	Soil, 1st rate. Good grass.
	May 20, 1871.
Field Notes of the Survey of Subdivisional lines of T.2 N.R.33 E., By Z. F. Moody, under his Contract No.145, Bearing date, April 23, 1871.	
North between Secs. 35 & 36.	
40.00	Set stone 15 x 15 x 4 for $\frac{1}{4}$ Sec. corner.
80.00	Set post and stone mound for corner to Secs. 35, 36, 25 & 26.
	Land, rolling.
	Soil, good 2nd rate. Good grass.
East on random between Secs.25 & 36.	
	Variation 21° East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.00	Intersected N & S line 10 N. of corner.
	N. 89° 56' West on true line.
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
60.50	Brook, 4 lks. flows N W.
80.00	To corner.
	Land, rolling.
	Soil, 2nd rate. Good grass.
North between Secs. 25 & 26.	
23.50	A Spring bears E. about 2 chains.
40.00	Set stone 14 x 12 x 4 for $\frac{1}{4}$ Sec. corner.
80.00	Set post and made mound of earth for corner to Secs. 25, 26, 23 & 24.
	Land, rolling.
	Soil, 2d rate. Good grass.