

Subdivisions, T. 2 N.R. 33 E.

Chains	
50.00	Enter river bottom.
80.54	To corner.
	Land, rolling.
	Soil, 2nd rate.
	May 24, 1871.
<hr/> North between Secs. 33 & 34.	
40.00	Set post and made earth mound for $\frac{1}{4}$ Sec. corner.
62.50	Tudie Willow 8 lks. flows N.W.
80.00	Set post and made mound of earth for corner to Secs. 33,
	34, 27, 28.
	Land, level.
	Soil, 1st rate.
<hr/> East on random between Secs. 27 & 34.	
	Var. 21° 30' East.
40.00	Set temporary $\frac{1}{4}$ Sec. post.
80.00	Intersected N & S line 14 N. of Corner.
	N. 89° 54' W. on true line.
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
80.00	To corner.
	Land, level.
	Soil, 1st rate.
<hr/> North between Secs. 27 & 28.	
40.00	Set post for $\frac{1}{4}$ Sec. corner and raised earth mound.
80.00	Set post and made mound of earth for cor. to secs. 27,
	28, 21, 22.
	Land, level.
	Soil, 1st rate.
<hr/> East on random between Secs. 22 & 27.	
	Var. 21° 30' East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.98	Intersected N & S line 14 N of corner.