

Subdivisions, T. 2 N. R. 33 E.

Chains	
	N.89° 54' W. on true line.
39.99	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
79.98	To corner.
	Land, level.
	Soil, 1st rate.
<hr/>	
	North between Secs. 21 & 22.
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
80.00	Set post and made mound of earth for corner to Secs. 21, 22, 16 & 15.
	Land, gently rolling.
	Soil, 2d rate.
<hr/>	
	East on random between Secs. 15 & 22.
	Var. 20° East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.14	Intersected N & S line 22 S. of corner.
	S. 89° 51' W. on true line.
40.07	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
80.14	To corner.
	Land, rolling.
	Soil, 1st rate.
<hr/>	
	North between Secs. 15 & 16.
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
60.00	LaGrand and Pendleton road E & W.
80.00	Set post and made mound of earth for corner to Secs. 15, 16, 9 & 10.
	Land, rolling.
	Soil, 2nd rate.
<hr/>	
	East on random between Secs. 10 & 15.
	Var. 20° 15' East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.90	Intersected N & S line 24 N of corner.