

## Subdivisions, T. 2 N. R. 33 E.

Chains	
	S. 89° 48' W. on true line..
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
80.00	To corner.
	Land, level.
	Soil, 1st rate.
<hr/>	
	North between Secs. 21 & 20.
32.50	Enter field. E & W.
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
45.00	Leave field. E & W.
80.00	Set post and made mound of earth for corner to Secs. 20, 21, 16 & 17.
	Land, level.
	Soil, 1st rate.
<hr/>	
	East on random line between Secs. 16 & 21.
	Var. 21° East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.00	Intersected N & S line 16 lks. S. of corner.
	S. 89° 53' W. on true line.
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
80.00	To corner.
	Land, level.
	Soil, 1st rate.
<hr/>	
	North between Secs. 16 & 17.
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
60.00	La Grand & Pendleton roads.
80.00	Set post and made mound of earth for corner to Secs. 16, 17, 8 & 9.
	Land, level.
	Soil, 1st rate.
<hr/>	
	East on random between Secs. 9 & 16.
	Var. 21° East.