

## Subdivisions, T. 2 N. R. 33 E.

Chains	
	<p>Land, level.</p> <p>Soil, 1st rate.</p> <p style="text-align: right;">May 26, 1871.</p>
	<p>North between Secs. 31 &amp; 32.</p>
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
80.00	Set post and made mound of earth for corner to Secs. 31, 32, 30 & 29.
	<p>Land, rolling.</p> <p>Soil, 1st rate.</p>
	<p>East on random between Secs. 29 &amp; 32.</p> <p style="text-align: right;">Variation 20° East.</p>
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.60	Intersected N & S line 19 lks. S. of corner. S. 89° 52' W. on true line.
39.80	Set post and made mound for $\frac{1}{4}$ Section corner.
79.60	To corner.
	<p>Land, level.</p> <p>Soil, 1st rate. Good grass.</p>
	<p>West on random between Secs. 30 &amp; 31.</p>
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.54	Intersected N & S line 14 links S. of corner. S. 89° 54' E. on true line.
39.54	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
79.54	To corner.
	<p>Land, level.</p> <p>Soil, 1st rate.</p>
	<p>North between Secs. 29 &amp; 30.</p>
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
80.00	Set post and made mound of earth for cor. to Secs. 29, 30, 19, 20.
	<p>Land, level.</p> <p>Soil, 1st rate. Good grass.</p>