

Subdivisions, T. 2 N. R. 33 E.

Chains	
	East on random between Secs. 20 & 29. Variation 20° 30' East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.14	Intersected N & S line 12 lks. N. of corner. N. 89° 55' W. on true line.
40.07	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
80.14	To corner. Land, rolling. Soil, 1st rate.
<hr/>	
	West on random between Secs. 19 & 30.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.80	Intersected N & S line at corner. East on true line.
39.80	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
79.80	To corner. Land, gently rolling. Soil, 1st rate. Good grass.
<hr/>	
	North between Secs. 19 & 20.
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
60.00	Enter Tudie Willow bottom.
80.00	Set post and made mound of earth for corner to Secs. 19, 20, 17, 18. Land, rolling. Soil, 1st rate.
<hr/>	
	East on random between Secs. 17 & 20. Variation 22° East.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.12	Intersected N & S line 14 N. of the corner. N. 89° 54' W. on true line.
40.00	Set post and made earth mound for $\frac{1}{4}$ Sec. corner.
50.00	Tudie Willow, flows N. W.
80.12	To corner. Land, level. Soil, 1st rate.