

## Subdivisions, T. 2 N.R. 33 E.

Chains	
	North on random between Secs. 5 & 6.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.60	Intersected N. boundary 14 links W. of corner. S.00° 06' W. true line.
40.60	Set stone 18 x 17 x 10 for $\frac{1}{4}$ Sec. corner.
70.00	Umatilla river, 250 links, flows W.
80.60	To corner. Land, level. Soil, 1st rate, from river bottom.
	May 29, 1871.
<hr/> Field Notes of the Survey of Sections in Tp. 2 N. R. No.33 E. Into Lots, by Zenas Moody, under Contract No. 164, Dated Oct. 4,1871.	
<hr/> Commenced at the Corner of Secs. 13, 24, 18 & 19 on Tp. line and ran North on E. boundary of Sec. 13.	
20.00	Set stone 10 x 10 x 9 for 1/16 S. corner and made mound of earth.
40.00	To $\frac{1}{4}$ Section corner.
60.00	Set post for 1/16 S. cor. and made earth mound.
80.00	To the section corner for Secs. 12, 13, 7 & 18 on Tp. line.
<hr/> North on East boundary of Sec. 12.	
20.00	Set post for 1/16 Sec. cor. and made earth mound.
23.54	To Umatilla River, flows W.
40.00	To S. line $\frac{1}{4}$ S. cor.
60.00	Set post and made stone mound for 1/16 Sec. cor.
80.00	To post for sec. cor.
<hr/> North on East boundary of Sec. 1.	
20.00	Set stone 10 x 10 x 7 for 1/16 S. Corner.
40.00	To post for $\frac{1}{4}$ S. cor.
60.00	Set post and made earth mound for 1/16 S. corner.
80.00	To Tp. corner.