

Allotments, T. 2 N. R. 33 E.

Chains	
	West on South boundary of Sec. 13.
10.00	Set post and made mound of earth for 1/32 S. corner.
20.00	Set post and made earth mound for 1/16 Sec. corner.
25.50	Dry bed of stream.
30.00	Set stone 17 x 14 x 5 for 1/32 S. cor.
40.00	To 1/4 Sec. corner.
	Thence
	North on random to the 1/4 S. corner on North boundary of Sec. 13.
80.00	Intersected N. boundary at 1/4 S. corner. S. on true line.
20.00	Set stone 17 x 10 x 5 for 1/16 S. corner.
40.00	Set temporary 1/4 S. corner.
46.00	Dry bed of stream.
60.00	Set stone 14 x 12 x 8 for 1/16 S. corner.
80.00	To corner.
	Thence
	West on S. bdy. of Sec. 13.
50.00	Set stone 19 x 10 x 7 for 1/32 S. corner.
60.00	Set stone 14 x 11 x 5 for 1/16 S. corner.
70.00	Set stone 12 x 12 x 10 for 1/32 S. corner.
79.90	To sec. cor.
	Thence
	North on West boundary of Sec. 13.
12.50	Wagon road.
20.00	Set post and made earth mound for 1/16 Sec. corner.
	Thence,
	E. on random from 1/16 S. cor. in S.W. Qr.
80.00	Intersected 1/16 S. corner on E. boundary at corner. W. on true line.
10.00	Set stone 12 x 10 x 8 for 1/32 S. corner.
20.00	Set stone 14 x 12 x 7 for 1/16 S. corner.
30.00	Set stone 14 x 10 x 9 for 1/32 S. corner.
40.00	To 1/16 S. corner.
50.00	Set stone 17 x 12 x 4 for 1/32 S. corner.