

## Allotments, T. 2 N. R. 33 E.

Chains	
	Thence
	East on random from 1/16 S. corner in S.W. Qr. to 1/16 S. corner on E. bdy. of Sec. 12.
80.06	Intersected E. bdy. 14 links S. of corner. S. 89° 54' W. on true line.
10.00	Set post for 1/32 S. cor. and made mound of earth.
20.00	Set stone 10 x 10 x 10 for 1/16 S. cor.
30.00	Set stone 14 x 10 x 5 for 1/32 S. cor.
40.03	To 1/16 Sec. cor. in S. half of Section.
50.00	Set post for 1/32 Sec. corner.
60.00	Set stone 10 x 10 x 4 for 1/16 Sec. corner.
70.00	Set stone 12 x 10 x 9 for 1/32 S. corner.
80.06	To 1/16 S. cor. on W. bdy. of Section.
	Thence
	North on W. bdy. of Sec. 12.
37.10	Enter river bottom.
40.00	To 1/4 Sec. corner.
	Thence
	E. on random from $\frac{1}{4}$ S. corner to $\frac{1}{4}$ Sec. corner on E. bdy. of Sec.
80.00	Intersected East bdy. at $\frac{1}{4}$ Sec. corner. W. on true line.
10.00	Set stone 14 x 12 x 7 for 1/32 S. corner.
20.00	Set post and made stone mound for 1/16 S. corner.
30.00	Set post and made earth mound for 1/32 Sec. corner.
34.00	To Umatilla River.
40.00	Set post and made earth mound for $\frac{1}{4}$ S. corner.
50.00	Set stone 19 x 15 x 8 for 1/32 S. corner.
60.00	Set stone 17 x 10 x 9 for 1/16 S. corner.
70.00	Set post for 1/32 S. corner.
80.00	To $\frac{1}{4}$ Sec. cor.
	Thence
	North on W. bdy. of Sec. 12.
60.00	Set post and made stone mound for 1/16 Sec. corner.
	Thence,