

## Allotments, T. 2 N., R. 33 E.

Chains	
	East on random from 1/16 Sec. cor. to 1/16 Sec. cor in E. bdy. of Sec. 12.
79.91	Intersected 1/16 Sec. corner at corner. W. on true line.
10.00	A Balm 8 in. diam. for 1/32 Sec. corner.
20.00	A stone 12 x 10 x 7 for 1/16 S. corner.
29.00	Enter Indian field.
30.00	Set stone 18 x 10 x 4 for 1/32 S. corner.
39.98	To 1/16 Sec. corner.
50.00	Set stone 12 x 11 x 9 for 1/32 S. corner.
60.00	Set post for 1/16 Sec. corner.
60.00	Leave field.
70.00	Set post for 1/16 Sec. corner.
72.00	Umatilla River.
79.96	To corner.
	Thence
	North on W. bdy. of Sec. 12.
63.40	To the Umatilla River.
80.00	To stone cor. to Secs. 1, 2, 11 & 12.
	Nov. 16, 1871.
	Thence
	East on random on N. bdy. of Section 12.
79.82	Intersected East bdy. of Section 44 lks. N of corner. N. 89° 38' W. on true line.
10.00	Set stone 12 x 12 x 10 for 1/32 S. corner.
20.00	Set post for 1/16 Sec. corner.
21.50	Enter Indian field.
30.00	Set post for 1/32 Sec. corner.
39.91	To $\frac{1}{4}$ Section corner.
	Thence
	North on random from $\frac{1}{4}$ Sec. cor. on N. bdy. of Sec. 12. To $\frac{1}{4}$ Sec. corner on N. bdy. of Sec. 1.
80.10	Intersected N. bdy at $\frac{1}{4}$ Sec. corner. South on true line.
20.00	Set stone 10 x 10 x 7 for 1/16 S. corner.