

Allotments, T. 2 N. R. 33 E.

Chains	
	East on random line from 1/16 Sec. corner in N.W. Qr. of Sec. 10 to 1/16 Sec. corner in N.E. Qr. of Sec. 10.
80.10	Intersected E. bdy. at 1/16 S. corner. W. on true line.
10.00	Set post in mound of stone for 1/32 S. corner.
20.00	Set post for 1/16 Sec. corner from which A Balm 12 ins. diam. bears S.88°E. 15 lks.
28.00	Enter Indian field.
30.00	Set post in stone mound for 1/32 S. corner.
40.05	To 1/16 Sec. corner.
50.00	Set post in mound of stone for 1/32 S. corner.
60.00	Set post in mound of stone 1/16 S. corner.
70.00	Set post in mound of stone for 1/32 S. corner.
80.10	To 1/16 Sec. corner.
	Thence
	North on West bdy. of Sec. 10.
75.00	Umatilla river.
80.00	To post for Sec. corner.
	Thence
	East on N. boundary of Sec. 10.
80.24	Intersected E. boundary of Section, 20 links S. of corner. S. 89° 51' W. on line.
70.00	Set post for 1/32 S. corner.
20.00	Set post in stone mound for 1/16 S. corner.
30.00	Set post in mound of stone for 1/32 S. corner.
40.12	To $\frac{1}{4}$ Sec. corner.
	Thence
	North from $\frac{1}{4}$ Section corner on N. boundary of Sec. 10 to $\frac{1}{4}$ Sec. corner on N. boundary of Sec. 3.
80.25	Intersected N. boundary at $\frac{1}{4}$ S. corner. S. on true line.
20.25	Set post for 1/16 S. corner.
40.25	Set temporary $\frac{1}{4}$ Sec. corner.
60.00	Set post for 1/16 S. corner.
80.25	To $\frac{1}{4}$ Sec. corner on S. boundary of Sec. 3.