

## Allotments, T. 2 N. R. 33 E.

Chains	
	East on random from 1/16 Sec. corner in N.W. Qr. Sec. 9 to 1/16 Section corner in N.E. Qr. Section 9.
80.06	Intersect East boundary of Sec. 9 at 1/16 Sec. corner. West on true line.
10.00	Set post in earth mounds for 1/32 Sec. corner.
20.00	" " " " " " 1/16 " "
30.00	" " " " " " 1/32 " "
40.03	To 1/16 Sec. corner.
50.00	Set post in earth mound for 1/32 Section corner.
60.00	" " " " " " 1/16 " "
70.00	" " " stone mound for 1/32 " "
80.06	To 1/16 Sec. corner. North on West boundary of Section 9.
72.50	Umatilla River 2.00 chains wide.
80.00	To Section corner. East on North boundary of Sec. 9.
80.10	Intersect East boundary of Sec. 9, 32 links South of corner.
	Thence
	S. 89° 47' W. on true line.
10.00	Set post for 1/32 Sec. corner from which A Balm 15 ins. diam. bears S.45° E. 25 links
20.00	Set post for 1/16 Section corner from which A Balm 10 ins. diam. bears N. 45° E. 25 links
30.00	Set post for 1/32 Sec. corner from which An Alder 8 ins. diam. bears S.60° E. 30 links
35.00	Enter Indian field.
40.05	To $\frac{1}{4}$ Section corner.
	Thence
	North from $\frac{1}{4}$ Section corner on South boundary of Sec. 4 to $\frac{1}{4}$ Section corner on North boundary of Sec. 4.
80.20	Intersect North boundary of Sec. 4 at $\frac{1}{4}$ Sec. corner. South on true line.
20.00	Set post in earth mound for 1/16 Sec. corner.
40.20	Set temporary $\frac{1}{4}$ Section corner.