

Allotments, T. 2 N., R. 33 E.

Section 6.

Chains	Sec. corner, marked 1/32 on W. face and raised a mound of stone over it. Pits impracticable. Land, gravelly.
	<hr/> From 1/32 Sec. corner 20 chs. W. and 10 chs. N. of 1/4 Sec. corner, between Secs. 6 & 7. I run West on random line in Sec. 6. Var. 20° East.
16.50	Intersect the West boundary of Tps. 3 lks. South of 1/32 Sec. corner. Thence, I run S. 89° 54' E. on true line in Sec. 6.
9.00	Leave grain field. Cross fence.
16.50	The 1/32 Sec. corner. Land, gravelly. Soil, 1st rate.
10.50	<hr/> From the 1/32 Sec. corner, 20 chs. W & 10 chs. N. of 1/4 Sec. corner between Secs. 6 & 7, I run East on true line in Sec. 6. Variation 19° East.
20.00	Foot of bluff, and ascend. Set stone 12 x 10 x 8 ins., 8 ins. in the ground for 1/32 Section corner, marked 1/32 on N. face and raised mound of stone over it. Pits impracticable. Land, gravelly on bottom. Rocky on bluff.
	<hr/> From the 1/16 Sec. corner 20 chains N. of the corner to Secs. 5, 6, 7 & 8, which is a charred stake, and pits 18 x 18 x 12 ins. N & S of stake 5½ ft. distant and mound of earth over it. In N. pit, a stake 2 ins. square, marked 1/16 S. on W. face, I run West on true line in Sec. 6. Var. 19° 30' East.