

## Allotments, T. 2 N., R. 33 E.

| Chains |   |     |
|--------|---|-----|
| 1.50   | Gulch, course S.  |     |
| 15.00  | " " "   | -50 |
| 20.00  | Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 Sec. corner, marked 1/16 on N. face, dug pits 18 x 18 x 12 ins. E & W of stone 5½ ft. distant and raised mound of earth 1½ ft. high, 3½ ft. base over it.  |     |
| 25.00  | Summit.   |     |
| 40.00  | Set basalt stone 12 x 8 x 7 ins., 8 ins. in the ground for 1/16 Sec. corner, marked 1/16 on N. face, dug pits 18 x 18 x 12 ins. E & W of stone, 5½ ft. distant and raised mound of earth 1½ ft. high, 3½ ft. base over it.  |     |
| 60.00  | Set a basalt stone 12 x 8 x 6 ins., 8 ins. in the ground for 1/16 Section corner, marked 1/16 on N. face and raised mound of stone 1½ ft. high, 3½ ft. base over it. Pits impracticable.<br>Land, broken and barren.  |     |
|        | From the ¼ Sec. corner, between Sections 5 & 6, which is a charred stake, and pits 18 x 18 x 12 ins. N & S of stake, 5½ ft. dist., and mound of earth over it. In N. pit a stake 2 ins. square marked ¼ S. on W. face, I run West on true line in the center of Section 6.<br>Variation 20° East. |     |
| 20.00  | Deposited charred stake 12 ins. in the ground for 1/16 Sec. corner, dug pits 18 x 18 x 12 ins., E & W of stake 5½ ft. distant and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on N. face. |     |
| 40.00  | Intersect the ¼ Sec. corner, which is a charred stake, 12 ins. in the ground with pits 18 x 18 x 12 ins. E & W of corner, 5½ ft. distant and mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit a stake 2 ins. square marked 1/4 S on N. face.  |     |