

## Allotments, T. 2 N., R. 33 E.

## Section 8.

Chains	
15.28	face. Dug pits 18 x 18 x 12 ins. N & S of stone, 5½ ft. dist. and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
20.00	Railroad course N. 85° W.
20.00	Enter timber.
30.00	Set stone 11 x 9 x 7 ins., 7 ins. in the ground for 1/16 Sec. corner marked 1/16 on W. face, from which A Balm 24 ins. diam. bears N. 30° W. 54 links dist., marked 1/16 S.B.T. and raised mound of stone over it.
	Land, bottom and bench. Bottom, rich. Grass, brush. Timber, balm.
	From the ¼ Sec. corner between Secs. 7 & 8, which is a charred stake and pits 18 x 18 x 12 ins. N & S of stake 5½ ft. distant and mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit, a stake 2 ins. square, marked ¼ S. on W. face. I run, North on true line between Secs. 7 & 8.
	Var. 21° East.
10.00	Set post 3 ft. long, 3 ins. square 24 ins. in the ground with marked stone for 1/16 Sec. corner, marked 1/16 S. on W. face. Dug pits 18 x 18 x 12 ins. N & S of post 5½ ft. distant, raised mound of earth 1½ ft. high, 3½ ft. base, around post.
20.00	Railroad, course N. 85° W.
22.00	Fence, course E & W.
30.00	Set post 3 ft. long, 3 ins. square, 24 ins. in the ground with marked stone, for 1/16 Sec. corner, marked 1/16 S. on W. face, dug pits 18 x 18 x 12 ins. N & S of post 5½ ft. distant and raised mound of earth 1½ ft. high, 3½ ft. base around post.
	Land, mostly level. Soil, 1st rate and partly cultivated. Some brush N of R.R.