

Chains	<p>10 chains North of <math>\frac{1}{4}</math> Sec. corner, between Secs. 8 &amp; 9.</p> <p style="text-align: center;">Thence I run,</p> <p>S.89° 43' W. on true line through Sec. 7. <span style="float: right;">Var.20°30'East.</span></p>
19.90	<p>Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 Sec. corner, marked 1/16 on N. face, dug pits 18x18x12 ins. E &amp; W of stone <math>5\frac{1}{2}</math> ft. distant, and raised a mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it.</p>
21.00	<p>Road, course S.W.</p>
39.80	<p>Set basalt stone 12 x 12 x 7 ins., 8 ins. in ground for 1/16 Sec. corner, marked 1/16 on N face; dug pits 18 x 18 x 12 ins. E &amp; W of stone <math>5\frac{1}{2}</math> ft. distant and raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it.</p>
55.80	<p>Road, course N. 88° W.</p>
59.70	<p>Set post, 3 ft. long, 4 ins. square, 24 ins. in ground with marked stone for 1/16 Sec.cor.,marked 1/16 S on N face; dug pits 18x18x12 ins.E &amp; W of post,<math>5\frac{1}{2}</math> ft. dist., and raised a mound of earth <math>1\frac{1}{2}</math> ft.high,<math>3\frac{1}{2}</math> ft.base around it.</p>
79.60	<p>To the 1/16 Sec. cor.,10 chs. N of <math>\frac{1}{4}</math> Sec. cor.,between Secs. 7 &amp; 8.</p> <p>Land, along the line, level. Soil, mostly ashy. Some thorn brush. But little grass.</p>
Section 9.	
	<p>From the 1/16 Sec. corner, 20 chains North of the <math>\frac{1}{4}</math> Sec. corner between Secs. 9 &amp; 10, which is a post 3 ft. long, 3 ins. square, firmly set in the ground, marked 1/16 S. on W. face, with pits 18x18x12 ins. N &amp; S of post <math>5\frac{1}{2}</math> ft. dist. and mound of earth <math>1\frac{1}{2}</math> ft. high,<math>3\frac{1}{2}</math> ft.base over it.</p> <p style="text-align: center;">Thence, I run</p> <p>North on true line between Sections 9 &amp; 10. <span style="float: right;">Var.20° East</span></p> <p>Through grain.</p>
10.00	<p>Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/32 Sec. corner, marked 1/32 on W face; dug pits 18 x 18 x 12 ins. N &amp; S of stone, <math>5\frac{1}{2}</math> ft. distant, and raised a mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it.</p> <p>Corner in draw and garden.</p> <p>Land, rolling. Soil, 1st rate. Cultivated.</p>