

Chains

Variation 20° East.

14.00	Bluff	-30
16.50	R. R., course S. 85° W.	
19.95	A balm tree, 5 ins. diam. in place, which I marked 1/32 S. on N. face for 1/32 Sec. corner, from which A Thorn 6 ins. diam. bears West 10 links distant, marked 1/32 S B T. A thorn 6 ins. diam. bears S. 45° East, 10 links distant, marked 1/32 S.B.T.	
25.00	Railroad, course N.W. curve.	
30.00	Bluff	+50
39.90	Deposited charred stake 12 ins. in the ground for 1/32 Sec. corner; dug pits 18 x 18 x 12 ins., E & W. of stake 5½ ft. distant and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In N. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/32 S. on N. face.	
45.00	Descend bluff.	
59.85	Set basalt stone 10 x 8 x 7 ins., 6 ins. in the ground for 1/32 Sec. corner, marked 1/32 on N. face and raised mound of stone over it. Pits impracticable.	-100
65.00	Ascend bluff.	
79.80	To the 1/32 Sec. corner, 10 chains N. of corner to Secs. 11, 12, 13 and 14. Land, broken over. Bluff-brush. Soil, 1st rate.	+ 75

Section 25.

To survey Sec. 25, there being a dispute about the line through center and N½ being surveyed, I began at 1/16 Sec. corner, 20 chs. S. of the N.W. corner, which is a charred stake 12 ins. in the ground; pits 18 x 18 x 12 ins. N & S of corner, 5½ ft. distant and mound of earth over it. In N. pit a stake 2 ins. square marked 1/16