

Allotments, T. 2 N.R. 33 E.

| Chains | |
|--------|--|
| 19.94 | <p>West on random line in Sec. 25.</p> <p>Var. 19° East.</p> <p>Setting temporary corner at 10 chains and at</p> <p>Intersect the W. boundary of Sec. 25 at 1/64 and 1/32 Sec. corner.</p> |
| 9.97 | <p>Thence, I run</p> <p>East on true line in Section 25.</p> <p>Variation 18° 30' East.</p> <p>Set stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/32 and 1/64 Sec. corner, marked 1/32 on N. and 1/64 on S. face and raised a mound of stone over it. Pits impracticable.</p> |
| 19.94 | <p>To the 1/32 Sec. corner.</p> <p>Line over a hill. Soil, mostly rocky. Some grass.</p> <p>From the 1/16 Sec. corner, 20 chs. E. of 1/16 Sec. corner and 20 chs. N. of corner to Secs. 25 & 26, 35 & 36.</p> <p>I run</p> <p>South on true line in Sec. 25.</p> |
| 10.00 | <p>Variation 19° East.</p> <p>Set stone 12 x 9 x 7 ins., 8 ins. in the ground for 1/64 Sec. corner, marked 1/64 on W. face and raised a mound of stone over it. Pits impracticable.</p> <p>Land in 10 acre lot on N.W. face of Mt. Mostly rocky on balance Soil 1st rate. Grass.</p> <p>Thence, I run</p> <p>East on true line in Sec. 25.</p> |
| 10.00 | <p>Variation 19° East.</p> <p>Descend.</p> <p>Set stone 12 x 9 x 7 ins., 8 ins. in the ground for 1/64 Sec. corner, marked 1/64 on N. face; dug pits 18x18x12 ins. E & W of stone, 5½ ft. distant and raised a mound of earth 1½ ft. high, 3½ ft. base over it.</p> <p>Land on N.W. face of Mt., mostly rocky on balance. Soil, 1st rate. Grass.</p> |