

Allotments, T. 2 N.R. 33 E.

Chains	
	<p>ins. N. & S. of stone $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p>
	<p>Land, mountainous.</p>
	<p>Soil, 1st rate. Grass, good.</p>
	<p>From the $\frac{1}{32}$ Sec. corner 10 chains N. and 20 chains E. of the $\frac{1}{4}$ Sec. corner between 35 & 36</p>
	<p>I run,</p>
	<p>West on random line in Sec. 36.</p>
	<p>Var. $20^{\circ}30'$ East.</p>
20.00	<p>Intersect the N & S line 5 lks. South of $\frac{1}{32}$ Sec. corner between Secs. 35 & 36.</p>
	<p>Thence, I run</p>
	<p>S. $89^{\circ}58'$ E. on true line in Sec. 36.</p>
	<p>Variation 20° East.</p>
	<p>Alongside hill to</p>
19.25	<p>Gulch, course N.W.</p>
20.00	<p>To $\frac{1}{32}$ Sec. corner.</p>
	<p>Land, mountainous.</p>
	<p>Soil, 1st rate. Grass, good.</p>
	<p>July 2d, 1889.</p>
	<p>My instructions calling for allotments in the $S\frac{1}{2}$ of Sec. 1 of this township, which is represented as having already been allotted under contract with Currin and Noland, I proceeded to examine said section and found that 40 acre tracts had been surveyed and corners established as set forth in the field notes of the former survey.</p>
	<p>General Description</p>
	<p>These lands are situated along the Umatilla River and foot hills of Blue Mountains, brushy and broken along the River and rolling on hills.</p>
	<p>Soil, mostly 1st rate. Partly cultivated by Indians.</p>