

T. 2. N. R. 33 E.

Chains	
	Land, mountainous 80.00 chains. Soil, 2nd rate. No timber. Good bunch grass.
	North on E. boundary Sec. 24. Variation 17°25' East.
6.00	Creek, course N. 10° W., 2 lks. wide.
11.00	Leave creek bottom.
20.00	Set a basalt stone 12 x 8 x 8 ins., 10 ins. in the ground for 1/16 Sec. corner, marked 1/16 on W. face and raised mound of stone alongside. Pits impracticable.
23.00	Top of ridge.
35.00	Foot of hill.
40.00	Set a basalt stone 16 x 6 x 6 ins., 10 ins. in ground for 1/4 Sec. corner, marked 1/4 on W. face; dug pits 18 x 18 x 12 ins. N & S of corner, 5 1/2 ft. distant; raised earth mound 1 1/2 ft. high, 3 1/2 ft. base alongside.
48.25	Wagon Road, course N.E.
56.75	" " " " "
60.00	Deposited a charred stake 12 ins. in ground for 1/16 Sec. corner; dug pits 18 x 18 x 12 ins. N & S of corner, 5 1/2 ft. distant; raised earth mound 1 1/2 ft. high, 3 1/2 ft. base alongside. In E. pit, drove a stake 24 x 2 x 2 ins., 12 ins. in the ground, marked 1/16 S. on W. face.
80.00	Set a basalt stone 9 x 8 x 7 ins., 6 inches in the ground for corner to Secs. 13, 18, 19 & 24. Marked 3 notches on N & S edges. Dug pits, 18 x 18 x 12 ins. in each Section, 5 1/2 ft. distant, raised earth mound 2 ft. high, 4 1/2 ft. base alongside.
	Land, rolling, 1st 35 chains; soil, 1st rate; next 45 chains, 1st rate. Grass short.
	North on E. boundary of Sec. 13. Variation 21° 15' East.
20.00	Deposited a charred stake 12 ins. in ground for 1/16 Sec.

+50