

T. 3 N. R. 33 E.

South Boundary

Chains	
40.00	Set a basalt stone 15 x 7 x 6 ins., 10 ins. in ground for 1/4 Sec. corner, marked 1/4 on W. face. Dug pits 18 x 18 x 12 ins. E. & W. of corner 5½ ft. distant, raised a mound of earth 1½ ft. high, 3½ ft. base along side.
48.10	Gulch, course N.E.
58.40	Wagon Road, course N.E. & S.W.
80.00	Set a basalt stone 10 x 8 x 7 ins., 6 ins. in the ground for corner to secs. 3, 4, 33 & 34, marked T. 3 N.S.34 on N.E. T. 2 N. S. 3 on S.E., R. 33 E. S. 4 on S.W., S. 33 on N.W. faces with 3 notches on E & W edges. Dug pits 18 x 18 x 12 ins. in each section, 5½ ft. distant, raised a mound of earth 2 ft. high, 4½ ft. base along side.
	Land, rolling.
	Soil, ashy, 2nd rate. Poor grass.
<p>South 89° 46' E. between Secs. 3 & 34.</p> <p style="text-align: right;">Variation 21° East.</p>	
11.00	Gulch, course S.W.
40.00	Deposited a charred stake 12 ins. in the ground for ¼ Sec. corner; dug pits 18 x 18 x 12 ins. E & W. of corner, 5½ ft. distant and raised a mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/4 S. on N. face.
80.00	Set post 48 x 4 x 4 ins. 12 ins. in the ground for corner to Secs. 2, 3, 34 & 35, marked T. 3 N.S. 35 on N.E. T. 2 N. S. 2 on S.E., R. 33 E. S. 3 on S.W. and S. 34 on N.W. faces with 2 notches on E. and 4 notches on W. edges; dug pits 18 x 18 x 12 ins. in each sec. 5½ ft. distant; raised a mound of earth 2 ft. high, 4½ ft. base around post.
	Land, rolling.
	Soil, ashy, 2nd rate. Poor grass.