

North Boundary Tp. 1 N., R. 33 E.
(S. Boundary, T. 2 N., R. 33-E.)

| Chains | Land, level. Soil, 2nd rate. No timber. Good grass. |
|--------|--|
| | <p>North 89° 57' E on N boundary of Sec. 5. Variation 20° East.</p> |
| 15.00 | Trail, course N. |
| 20.00 | <p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. corner; dug pits 18x18x12 ins. E & W of corner, 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it. In E pit, drove a stake 2 ft. long, 2 ins. square, 12 ins. in ground, marked 1/16 S on W. face.</p> |
| 21.20 | Tudie Willow Creek, course N. |
| 23.50 | Trail, course N.W. |
| 40.00 | <p>Deposited a charred stake 12 ins. in the ground for ¼ Sec. corner; dug pits 18x18x12 ins. E & W of corner, 5½ ft. dist. Raised earth mound 1½ ft. high, 3½ ft. base over it. In E. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ¼ S. on W. face.</p> |
| 43.40 | Trail, course N.W. |
| 60.00 | <p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. corner; dug pits 18x18x12 ins. E & W of corner, 5½ ft. distant, raised mound of earth 1½ ft. high, 3½ ft. base over it. In E. pit, drove a stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked 1/16 S on W. face.</p> |
| 68.00 | Trail, course N.W. |
| 80.00 | <p>Set a post 48x4x4 ins. 2 ft. in the ground for corner to secs. 4, 5, 32 & 33. Deposited a charred stake with post marked T.1 N.S.5 on S.W., R.33E.S4 on S.E., T.2 N.S.33 on N.E., S.32 on N.W. faces with 2 notches on W and 4 on E edges. Dug pits 18x18x12 ins. in each Sec. 5½ ft. dist. Raised earth mound 2 ft. high, 4½ ft. base around it.</p> |
| | <p>Land, level. Soil, 2nd rate. No timber, good grass.</p> |
| | <p>North 89° 57' E on N boundary of Sec. 4. Variation 20° East.</p> |