

Subdivisions, T. 2 N., R. 33 E.

Chains		
79.50	<p>Descend gradual slope.</p> <p>Cor. to secs. 25, 26, 35 and 36.</p> <p>Land, mountainous 79.50 chs.</p> <p>Soil, 3rd rate. Considerable shell rock. Poor grass.</p>	
10.00	<p>North bet. secs. 25 and 26.</p> <p style="text-align: right;">Variation 20° East.</p> <p>Top of ridge, W.</p>	-40
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. N & S of stake, 5½ ft. dist. Raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W face.</p>	
24.10	<p>Wagon road N.W.</p>	
40.00	<p>Deposited charred stake 12 ins. in the ground for 1/4 sec. corner; dug pits 18 x 18 x 12 ins. N & S of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked ¼ S on W face.</p>	
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. N & S of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long 2 ins. square, 12 ins. in the ground, marked 1/16 S. on W. face.</p>	
68.50	<p>Wagon road N.W.</p>	
80.00	<p>Deposited charred stake 12 ins. in the ground for corner to secs. 23, 24, 25 and 26; dug pits 18 x 18 x 12 ins. in each sec. 5½ ft. distant; raised mound of earth 2 ft. high, 4½ ft. base over it and in S. E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked T 2 N S 24 on N.E., R. 33 E. S 25 on S.E., S 26 on S.W. and S 23 on N.W. faces with 2 notches on S and 1 notch on E ridges.</p> <p>Land, rolling. Soil, 1st rate. Fair agricultural land.</p>	