

## Subdivisions, T. 2 N., R. 33 E.

Chains	
80.00	<p>East on random between secs. 24 and 25.</p> <p style="text-align: right;">Variation <math>18\frac{1}{2}^{\circ}</math> East</p> <p>Set temporary corners at 20, 40 and 60 chains and at Intersect E. bdy. of Township 10 lks. S. of corner to secs. 24, 25, 19 and 30.</p> <p style="text-align: center;">Thence</p> <p>S. <math>89^{\circ} 56'</math> W. on true line.</p>
20.00	<p style="text-align: right;">Variation <math>17^{\circ}25'</math> East</p> <p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 Sec. cor. marked 1/16 S on N. face; dug pits 18 x 18 x 12 ins. E &amp; W of post <math>5\frac{1}{2}</math> ft. distant; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it.</p>
21.50	Enter field adjoining Indian School.
29.50	Leave same N & S.
34.00	Wagon road to Catholic Church N. about 8.00 chains..
35.36	Enter field and garden N & S.
40.00	<p>Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground near edge of garden for <math>\frac{1}{4}</math> Sec. corner, marked 1/4 on N. face; dug pits 18 x 18 x 12 ins. E &amp; W of stone <math>5\frac{1}{2}</math> ft. distant; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and from which school building bears N.W. about 8.00 chains.</p>
56.00	Leave field and garden N & S.
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E &amp; W of stake <math>5\frac{1}{2}</math> ft. dist. Raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
66.50	School house bears N.E.
80.00	<p>Pendleton and LaGrande Wagon road, N.</p> <p>Cor. to Secs. 23, 24, 25 and 26.</p> <p>Land, slightly rolling.</p> <p>Soil, 1st rate.</p> <p>Mostly cultivated.</p>