

Subdivisions, T. 2 N., R. 33 E.

Chains	
	North bet Secs. 23 & 24.
	Variation $18\frac{1}{2}^{\circ}$ East.
6.50	Wagon road S.W.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked 1/16 S. on W. face.
20.10	Wagon road, N.W.
23.09	Pendleton & LaGrande Wagon Road, N.W.
25.00	Old road, E & W.
40.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. corner; dug pits 18 x 18 x 12 ins. N & S of stake, $5\frac{1}{2}$ ft. dist.; raised mound of stone and earth over it $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft base and in N. pit drove stake 2 feet long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S. on W. face.
41.70	Old wagon road N.W.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. North & S of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ feet high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S. on W. face.
75.10	Wagon road N.W.
80.00	Set post 4 ft. long, 4 ins. square 24 ins. in the ground for cor. to secs. 13, 14, 23 and 24, marked T.2 N.S.13 on N.E., R.33 E. S.24 on S.E., S. 23 on S.W. and S. 14 on N.W. faces with 3 notches on S. and 1 notch on E. edges; dug pits, 18 x 18 x 12 ins. in each sec. $5\frac{1}{2}$ ft. dist., and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.
	Land, level.
	Soil, 1st rate. No grass.