

Subdivisions, T. 2 N. R. 33.

Chains		
	East on random between Secs. 13 and 24.	
	Variation 20° East.	
	Set temporary cors. at 20, 40 and 60 chains and at	
30.00	Intersect E. bdy. of Township 10 lks. S. of cor. to secs. 18, 19, 13 & 24.	
	Thence	
	So. 89° 56' West on true line.	
	Variation 21¼° East.	
20.00	Set basalt stone 10 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face; dug pits 18x18x12 ins. E & W of stone 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it.	
23.50	Gulch N.	-25
29.00	Wagon road N.E.	
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked ¼ S on N face.	
58.00	Wagon road N.W.	
60.00	Drove charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground; marked 1/16 S on N. face.	
80.00	Cor. to secs. 13, 14, 23 and 24.	
	Land, mostly level. Soil, 1st rate. Grass, good. Can all be cultivated.	
	North bet. secs. 13 and 14.	
	Variation 20° East.	
	Set post 3 ins. square 3 ft. long, 24 ins. in the ground for 1/16 sec. cor., marked 1/16 S. on W. face; dug pits 18 x 18 x 12 ins. N & S of post 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it.	