

Subdivisions, T. 2 N., R. 33 E.

Chains	
20.30	Wagon road N.E.
39.90	Deposited charred stake 12 in. in the ground for $\frac{1}{4}$ Sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S on N face.
59.85	Set basalt stone 10 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on N face; dug pits 18 x 18 x 12 ins. E & W of stone $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
77.00	Spring branch 2 lks N.
79.80	Cor. to secs. 11, 12, 13 and 14. Land, rolling. Soil, generally good. Can most all be cultivated.
North between secs. 11 and 12.	
Variation 20° 10' East.	
5.25	Thorn thicket E & W.
15.00	Leave same.
17.00	Wagon road E & W.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked 1/16 S on W face.
34.00	Enter Grave yard.
38.25	Brink of bluff and leave grave yard.
40.00	Set boulder rock 8 x 8 x 8 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W face; raised mound of stone over it.
40.75	O.R. & N. Railway N.W.
50.00	Umatilla river W 100 lks. wide.
80.00	Set basalt stone 12 x 8 x 6 ins., 8 ins. in the ground for cor. to secs. 1, 2, 11 and 12, marked with 5 notches on