

Subdivisions, T. 2 N., R. 33 E.

Chains

S and one notch on E edges and raised a mound of stone over it.

Land, rolling, somewhat rough.

Soil, 2nd rate on rolling land, 3rd rate in bottom.

Timber: Balm, thorn & pine along river, and considerable underbrush.

Grass, fair.

Only part of this mile can be cultivated.

East on random between secs. 1 and 12.

Variation $20\frac{1}{4}^{\circ}$ East.

Set temporary corners at 20, 40 & 60 chains and at

80.02 Intersect E. bdy. Township 20 lks. S of cor. to secs. 6, 7, 1 and 12.

Thence

S. $89^{\circ} 51'$ W. on true line.

Variation $19\frac{1}{4}^{\circ}$ East.

20.00 Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake, $5\frac{1}{2}$ ft. dist.; raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 inches in the ground, marked $\frac{1}{16}$ S on N. face.

40.01 Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S. on N. face.

60.01 Set basalt stone 10 x 8 x 8 ins., 6 ins. in the ground for $\frac{1}{16}$ sec. cor., marked $\frac{1}{16}$ on N. face; dug pits 18 x 18 x 12 ins. E & W of stone, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.

61.50 Fence N & S.

71.30 Stream 60 lks. S. W.

80.02 Cor. to secs. 1, 2, 11, 12.

Land, rolling. Soil, 1st rate. Can be cultivated S. of