

Subdivisions, T. 2 N., R. 33 E.

Chains	<p>raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked <math>\frac{1}{4}</math> S on W. face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. corner; dug pits 18x18x12 ins. N &amp; S of stake <math>5\frac{1}{2}</math> ft. dist.; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W face.</p>
79.00	<p>Wagon road N.E. and S.W.</p>
80.00	<p>Set post 4 ft. long, 4 ins. square 24 ins. in the ground for cor. to secs. 22, 23, 26 and 27, marked T2N S23 on N.E., R33E S26 on S.E., S27 on S.W. and S22 on N.W. faces with 2 notches on S and E edges. Dug pits 18x18x12 ins. in each sec. <math>5\frac{1}{2}</math> ft. dist.; raised mound of stone and earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it. Land, level. Soil, generally 1st rate. Some rock. Grass short.</p>
<p>East on random between secs. 23 and 26.</p>	
<p>Variation <math>20^{\circ}</math> East.</p>	
79.80	<p>Set temporary cors. at 20, 40 and 60 chains and at Intersect N &amp; S line at cor. to secs. 23, 24, 25 and 26. Thence,</p>
<p>West on true line</p>	
<p>Variation <math>18\frac{1}{2}^{\circ}</math> East.</p>	
19.95	<p>Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for 1/16 Sec. corner, marked 1/16 S on N face; dug pits 18x18x12 ins. E &amp; W of post <math>5\frac{1}{2}</math> ft. dist.; raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base around post.</p>
24.10	<p>Wagon road N.</p>
39.90	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> sec. cor.; dug pits 18x18x12 ins. E &amp; W of stake <math>5\frac{1}{2}</math> ft. dist. raised mound of earth <math>1\frac{1}{2}</math> ft. high, <math>3\frac{1}{2}</math> ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked <math>\frac{1}{4}</math> S on N face.</p>