

## Subdivisions, T. 2 N., R. 33 E.

Chains		-20
27.25	Gulch N.	
39.87	Set basalt stone 16 x 10 x 6 ins., 10 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face; dug pits 18 x 18 x 12 ins. E & W of stone $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
51.00	Gulch N.E.	
53.00	Wagon road N.E.	
59.80	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face; dug pits 18 x 18 x 12 ins. E & W of stone, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
72.00	Wagon road N.	
79.74	Cor. to secs. 10, 11, 14 and 15. Land, rolling and high. Soil, a kind of ashy or alkali fine loam, 3rd rate. Grass poor.	
<hr/> North between secs. 10 and 11.		
Var. $20-3/4^{\circ}$ East		
12.80	Wagon road E & W.	
14.30	Brink of bluff 30 ft. high. Descend.	
15.30	Spring branch 6 lks. N.	
20.00	Set basalt stone 16 x 8 x 7 ins., 10 ins. in the ground for 1/16 sec. cor., marked 1/16 on W. face; raised mound of stone over it.	
37.30	Wagon road E & W.	
40.00	Set basalt stone 10 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor.; marked $\frac{1}{4}$ on N. face; dug pits 18 x 18 x 12 ins. E & W of stone $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
50.40	O.R. & N. Railway S.W.	
60.00	Set stone - 20 x 16 x 16 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face and raised mound of stone over it.	