

Subdivisions, T. 2 N., R. 33 E.

Chains	
67.50	Umatilla River bed. Water in channel.
70.00	Leave same.
80.00	An alder 5 ins. diam., which I mark T2N S2 on NE, R33E S11 on SE., S10 on S.W. and S3 on N.W. faces for cor. to secs. 2, 3, 10 and 11 marked with 5 notches on S and 2 notches on E edges, from which An alder 5 ins. diam. bears N. 35° E. 4 lks. dist., marked T2 NR33E S2 B.T. An alder 4 ins. diam bears S. 40° E. 2 lks dist., marked T2 NR33E S11 B.T. An alder 5 ins. diam. brs. S. 40° W. 2 lks. dist., marked T.2 N.R. 33 E.S.10 B.T. An alder 5 ins. diam. brs. N. 45° W. 1 lk. dist., marked T.2 N.R. 33 E. S. 3 B.T. Land, rolling. Soil generally 1st rate. Heavy timber: Cottonwood and alder along river 56.70 chs. Aug. 29th, 1887.
	East on random between secs. 2 and 11. Variation 20° East. Set temporary cors. at 20, 40 and 60 chains and at 79.70 Intersect N & S line at cor. to secs. 1, 2, 11 and 12. Thence, West on true line. Var. 20½° East.
19.92	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18x18x12 ins. E & W of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in East pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.
39.85	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for ¼ sec. cor. marked ¼ S on N face from which a A Cottonwood 16 ins. diam. bears N.65° E. 54 lks dist. marked ¼ S. B. T. A Cottonwood 24 ins. diam. bears South 32 lks. dist.