

Subdivisions, T. 2 N., R. 33 E.

Chains	
	for 1/16 sec. cor. marked 1/16 S on W. face; dug pits 18x18x12 ins. N & S of post 5½ ft. distant, raised mound of stone and earth 1½ ft. high 3½ ft. base over it.
71.00	Enter brush.
75.00	Spring branch 20 lks. W.
75.84	Cor. to secs. 2, 3, 10 and 11. Land, rolling. Soil, fair. Brush in bottom.
North bet. secs. 33 and 34.	
Variation 21° East.	
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. N and S of stake 5½ ft. dist., raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S on W. face.
40.00	Deposited charred stake 12 ins. in the ground for 1/4 sec. corner; dug pits 18 x 18 x 12 ins. N and S of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked 1/4 S on W. face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. N and S of stake, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W face.
77.00	Dry bed of Tudie Willows Creek, N.E.
80.00	Set post 4 ft. long, 4 ins. square 24 ins. in the ground for corner to secs. 27, 28, 33 and 34 marked T2NS27 on N.E., R33E.S34 on S.E., S33 on S.W. and S28 on N.W. faces with 1 notch on S and 3 notches on E edges.