

Subdivisions, T. 2 N., R. 33 E.

Chains	
	North between secs. 27 and 28. <div style="text-align: right;">Variation 20° East.</div>
1.50	Tudie Willows Creek, Dry, N.W.
10.50	Wagon road E & W.
20.00	Set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. N and S of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it.
40.00	Deposited charred stake 12 ins. in the ground for ¼ sec. corner; dug pits 18 x 18 x 12 ins. N & S of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked ¼ S on W face.
43.00	Wagon road E & W.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins N & S of stake 5½ ft. distant; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long 2 ins. square, 12 ins. in the ground, marked 1/16 S on W face.
68.75	Wagon road N.W.
80.00	Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for corner to secs. 21, 22, 27 and 28, marked T2NS22 on N.E.; R33ES27 on S.E.; S28 on S.W. and S21 on N.W. faces with 2 notches on S and 3 notches on E edges; dug pits 18 x 18 x 12 ins. in each section 5½ ft. distant; raised mound of earth 2 ft. high, 4½ ft. base over it.
	Land, level.
	Soil, 1st rate. Poor grass. Well adapted to agriculture.
	East on random between secs. 22 and 27. <div style="text-align: right;">Variation 19-3/4° E.</div>
79.80	Set temporary corners at 20, 40 and 60 chains and at Intersect N and S line at corner to secs. 22, 23, 26 and 27.