

Subdivisions, T. 2 N., R. 33 E.

Chains		
40.00	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W face; dug pits 18 x 18 x 12 ins. N and S of stone $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
53.00	Foot of hill. Ascend.	
60.00	Top of hill E & W and set post 3 ft. long, 3 ins. square 24 ins. in the ground for 1/16 sec. corner, marked 1/16 S on W face; dug pits 18 x 18 x 12 ins. N and S of corner $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around it.	+100
76.00	Wagon road E & W.	
80.00	Deposited charred stake 12 ins. in the ground for corner to secs. 15, 16, 21 and 22; dug pits 18 x 18 x 12 ins. in each section, $5\frac{1}{2}$ ft. dist.; raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it and in S. E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked T2N S15 on N.E., R33E S22 on S.E., S21 on S.W. and S16 on N.W. faces, with 3 notches on S and E edges. Land, mostly level. Soil, 1st rate. All suited for agriculture.	
	East on random between secs. 15 and 22.	
	Variation $20\frac{1}{4}^{\circ}$ East.	
	Set temporary corners at 20, 40 and 60 chains and at	
80.20	Intersect N and S line 15 lks. S of corner to secs. 14, 15, 22 and 23.	
	Thence	
	S. $89^{\circ} 53'$ W on true line.	
	Variation 20° East.	
6.90	Wagon road N.E.	
20.05	Deposited charred stake 12 ins. in the ground for 1/16 sec. corner; dug pits 18 x 18 x 12 ins. E & W of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E pit drove stake 2 ft. long, 2 ins.	