

Subdivisions, T. 2 N., R. 33 E.

Chains

- ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $1/16$ S on N face.
- 24.70 Fence and enter field. N.W.
- 40.00 Drove charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake $5\frac{1}{2}$ ft. dist.; raised mound of stone and earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked $1/4$ S on N face.
- 60.00 Deposited charred stake 12 ins. in the ground for $1/16$ sec. corner; dug pits 18 x 18 x 12 ins. E & W. of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S on N. face.
- 78.30 Fence N.E. and leave field.
- 80.00 Corner to secs. 20, 21, 28 and 29.
Land, level.
Soil, 1st rate.
Well adapted to agriculture.
-
- North between secs. 20 & 21.
Variation 20° East.
- 13.50 Road E & W.
- 20.00 Deposited charred stake 12 ins. in the ground for $1/16$ sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it & in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S on W. face.
- 31.00 Wagon road E & W.
- 39.60 Old ditch fence N.E.
- 40.00 Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. corner; dug pits 18 x 18 x 12 ins. N & S of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N pit drove stake 2 ft. long, 2 ins.