

Chains	
40.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{2}$ sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked $\frac{1}{2}$ S on W face.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W face.
80.00	Deposited charred stake 12 ins. in the ground for corner to secs. 29, 30, 31 and 32; dug pits 18 x 18 x 12 ins. in each sec. $5\frac{1}{2}$ ft. dist.; raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it and in S.E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked, T2N S29 on N.E.; R33E S32 on S.E.; S31 on S.W. and S30 on N.W. faces with 1 notch on S and 5 notches on E. edges. Land, level. Soil, 1st rate. All good agricultural land.
80.00	East on random between secs. 29 and 32. Variation 21° East. Set temporary corners at 20, 40 and 60 chains and at Intersect N & S line 12 lks. N of cor. to secs. 28, 29, 32 and 33. Thence N. 89° 55' W. on true line. Variation same.
5.90	Wagon road N.W.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.