

Subdivisions, T. 2 N., R. 33 E.

Chains	
25.00	Ditch fence and enter field.
40.00	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. corner; dug pits 18 x 18 x 12 ins. E & W of stake, $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S on N face. House bears N.E. about 8 chains.
40.25	Rail fence and leave field N & S.
60.00	Deposited charred stake 12 ins. in the ground for $1/16$ sec. corner; dug pits 18 x 18 x 12 ins. E & W of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground marked $1/16$ S on N. face.
80.00	Cor. to secs. 29, 30, 31 and 32. Land, rolling. Soil, 1st rate. All good agricultural land.
	West on true line between sections 30 and 31. Var. 21° East
20.00	Deposited charred stake 12 ins. in the ground for $1/16$ sec. corner; dug pits 18 x 18 x 12 ins. E & W of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $1/16$ S on N face.
35.65	Wagon road S.
40.00	Deposited charred stake 12 ins. in the ground for $1/16$ sec. corner; dug pits 18 x 18 x 12 ins. E & W of stake $5\frac{1}{2}$ ft. distant; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S on N face.
60.00	Deposited charred stake 12 ins. in the ground for $1/16$ sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake $5\frac{1}{2}$ ft. dist.; raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft.