

Subdivisions, T. 2 N., R. 33 E.

Chains	
	<p>3½ ft. base over it, and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
21.75	Wagon road E and W.
40.00	<p>Drove charred stake 12 ins. in the ground for ¼ section cor.; dug pits 18 x 18 x 12 ins. N and S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked ½S on W. face.</p>
45.00	Fence and enter field E & W.
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N and S of stake 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on W. face.</p>
80.00	<p>Deposited charred stake 12 ins. in the ground for cor. to secs. 17, 18, 19 and 20; dug pits 18 x 18 x 12 ins. in each sec. 5½ ft. dist.; raised mound of earth 2 ft. high, 4½ ft. base over it and in S.E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked T2N S17 on N.E.; R33E S20 on S.E.; S19 on S.W., and S18 on N.W. faces, with 3 notches on S and 5 notches on E. edges.</p> <p>Land, gently rolling. Soil, 1st rate. Well adapted to agriculture.</p>
	<hr/> <p>East on random between secs. 17 and 20.</p> <p style="text-align: right;">Variation 19° East.</p>
79.80	<p>Set temporary corners at 20, 40 and 60 chains and at Intersect N and S line 12 lks. S of corner to secs. 16, 17, 20 and 21.</p> <p style="text-align: center;">Thence</p> <p>S. 89° 55' W. on true line.</p> <p style="text-align: right;">Variation 21° East.</p>