

| Chains | |
|--------|--|
| 60.00 | Deposited charred stake 12 ins. in the ground for 1/16 |
| | sec. cor.; dug pits 18 x 18 x 12 ins. N and S of stake |
| | 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. |
| | base over it and in N pit drove stake 2 ft. long, 2 ins. |
| | square 12 ins. in the ground marked 1/16 S on W. face. |
| 66.30 | Old Emigrant wagon road W. |
| 80.00 | Deposited charred stake 12 ins. in the ground for cor. to |
| | secs. 7, 8, 17 and 18; dug pits 18 x 18 x 12 ins. in each |
| | sec., 5 1/2 ft. dist.; raised mound of earth 2 ft. high, 4 1/2 |
| | ft. base over it and in S.E. pit drove stake 2 ft. long, |
| | 2 ins. square 12 ins. in the ground, marked T2NS8 on N.E. |
| | R33E S17 on S.E.; S18 on S.W. and S7 on N.W. faces with |
| | 4 notches on S and 5 notches on E. edges. |
| | Land, rolling. Soil, 1st rate. Good agricultural land. |
| 79.60 | Intersect N and S line 15 lks. N of cor. to secs. 8, 9, 16 |
| | and 17. |
| | Thence |
| | N. 89° 53' W. on true line. |
| | Variation 21° East. |
| 12.00 | Small gulch N. |
| 14.25 | Wagon road N.W. |
| 19.90 | Deposited charred stake 12 ins. in the ground for 1/16 |
| | sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake |
| | 5 1/2 ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. |
| | base over it and in East pit drove stake 2 ft. long, 2 |
| | ins. square 12 ins. in the ground marked 1/16 S on N |
| | face. |
| 39.80 | Deposited charred stake 12 ins. in the ground for 1/16 |
| | sec. cor.; dug pits 18 x 18 x 12 ins. E and W of stake 5 1/2 |
| | ft. dist.; raised mound of earth 1 1/2 ft. high, 3 3/4 ft. base |
| | over it and in E pit drove stake 2 ft. long, 2 ins. |